



TSC-400-□□□ Safety test result
TSC-600-□□□

Approved : Tadayuki Hoda

Prepared : Yuichi Matsuto

No.	Test item	Conditions	Conditions of acceptability	Result
1	Overload test	(1)Overload. 135% of current rating. (2)Ambient temp. 25±5°C (3)Test period rated current ≤ 81A : 1 hour rated current > 81A : 2 hours	(1)Evidence of ignition , sealant leakage , cracking , breakage , or similar physical damage is not shown. (2)When a test voltage is applied , isolation resistance is not less than 3.5MΩ (Without discharge resistor). Test voltage rated voltage ≤ 250V : 250 V dc rated voltage > 250V : 500 V dc	OK
2	Withstand voltage test (High-pot test)	(1) Input Not applied. (2) Ambient temp. 25±10°C (3) The applied voltage is 1.4 times of specifications.	(1)Insulation breakdown , flashover or electric arc is not occurred.	OK
3	Isolation resistance test (without code -665)	(1)Input Not applied. (2)Ambient temp. 25±10°C	(1)When a regulation voltage is applied, isolation resistance is 1.4 times of specifications.	OK
4	Vibration/impact test	Vibration (1)f=10~150Hz : 14.7m/s ² (2)3 minutes period (3)60 minutes along X, Y and Z axis Impact (1)147.2m/s ² 11ms (2)Once each X, Y and Z axis	(1)No degradation of electric characteristics after test. (2)No crack at solder joint. (3)No marked damage of appearance.	OK